BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division

No.BBMP/EE/DD/Ten/07/2016-17, Date:11.01.2017 ITEM NO:25

SCHEDULE-B

NAME OF THE WORK: Providing and fixing street name boards in Bagalagunte ward no. 14 Dasarahalli sub division

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor V.Mohan kumar	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per the direction of Engineer-in-charge of the work	Cum	32.54	86.92	Rupees Eighty Six and Ninety Two Paise Only
2	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km complete as per the direction of Engineer-in-charge of the work	Cum	32.54	74.40	Rupees Seventy Four and Forty Paise Only
3	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregares @ 0.465 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. complete as per the direction of Engineer-in-charge of the work	Cum	8.14	5348.76	Rupees Five Thousand Three Hundred Forty Eight and Seventy Six Paise Only

V. Mohan Kumar

Signature of the Contractor

Executive Engineer
Dasarahalli Division

4.	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregares @ 0.43 cum with superplastisiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, complete as per the direction of Engineer-in-charge of the work	Cum	24.41	5874.52	Rupees Five Thousand Eight Hundred Seventy Four and Fifty Two Paise Only
5	Supplying of MS steel name boards as per approved design and specification complete with all leads and lifts as per the direction of the Engineer-in-charge of the work (Data rate approved) complete as per the direction of Engineer-in-charge of the work	No	113.00	5203.00	Rupees Five Thousand Two Hundred Three Only
6	Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications. complete as per the direction of Engineer-in-charge of the work	sqm	118.20	86.92	Rupees Eighty Six and Ninety Two Paise Only
7	Applying red lead ready mix priming coat over new steel or other metal surface including preparing the surface after thoroughly cleaning oil, grease, dirt and other foreign matter, and scoured with wire brushes, fine steel wool, sand papers including cost of materials, laour complete as per specifications. complete as per the direction of Engineer-in-charge of the work	sqm	118.20	30.74	Rupees Thirty and Seventy Four Paise Only
8	Painting new letter and figures of any shade with synthetic enamel paint black or nay other approved colour to give an even shade complete as per specifications ("ii) Hindi (Matras commas and the like not to be measured and paid for half letter shall be counted as half) . complete as per the direction of Engineer-in-charge of the work	cm	235500.00	0.795	Seventy Nine Paise Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

Executive Engineer
Dasarahalli Division